



PANEL REINFORCEMENT TYPE-PW-1 (NTS)  
PANEL THICKNESS AS NOTED  
2PP-80 REINFORCEMENT

MANUFACTURE	
SETUP:	
BED No:	
CAST:	
BUILT BY:	
PREPPED BY:	
QA'D BY:	
HARDWARE	OFF
M20 N.F. [FIXING] REID FE20095	
M20 F.F. [FIXING] REID FE20095	10
M20 Double [FIXING] REID FE20095	
M20 N.F. [PROP]	
M20 F.F. [PROP]	2
M16 N.F. [FIXING]	
M16 F.F. [FIXING]	
M20 EDGE FERRULE	
CAST-INS	OFF
7t LIFTER EDGE REID SJS	2
GROUT TUBE DOWN.	
GROUT TUBE UP.	
MISCELLANEOUS	
PANEL I.D PLATE	
C.O.G. LIFTING CENTROID X	
EXPOSED EDGE	

Client: AMARCOM GROUP PTY LTD		AREA (m2)	5.8	THICKNESS	150	Project:  PROPOSED DEVELOPMENT				
	AMARCOM Group Pty Ltd PRECAST PANEL DIVISION. 18-20 Lucca RD, Wyong, NSW, 2259. PH:02 4352 2468 FAX: 02 4353 1255.	VOL. (m3)	0.9	ConcRete(MPa)	40 MPa	AT 43 ACCOLADE AVE. MORRISSET NSW 2264		02	Issued For Construction	15/12/2021
		WT (T)	2.18	C of GRAVITY	X 1770		Prepared By: WFJ ENGINEERING Co. PTY LTD ABN-33 078 373 985 Structural Engineering Design & Detailing Drafting SUITE-5 LEVEL-1/221 MILLER ST NORTH SYDNEY 2060 Tel: (02) 8004 0741 Fax: (02) 9957 4237 E-mail: wfjeng@ozemail.com.au	01	ISSUED FOR FABRICATION	04/12/2021
		REO.	AS SHOWN 30 COVER		Y 822			B	ISSUED FINAL FOR APPROV	20/11/2021
								A	ISSUED FOR APPROVAL	19/10/2021
								Drawn		Date
								Checked		Scale 1:50
								Project No.	DWG / PANEL No.	Rev.
								3576	2PP-80	02